

MANUFACTURED HOME PERMIT GUIDE



www.talbotcountymd.gov

28712 Glebe Road, Suite 1
Easton, MD 21601
410-770-6840

The Department of Permits and
Inspections
Talbot County, Maryland

Conditions

- No new single-wide Manufactured Homes are allowed in Talbot County except that an existing single-wide manufactured home may be replaced.
- The following standards apply for the placement of double-wide manufactured homes permitted as single-family residences on individual lots or parcels. These standards are not applicable to Manufactured Homes located in a Manufactured Home Rental Community or Manufactured Home Subdivision located within a Manufactured Home Floating Zone. These standards are also not applicable to manufactured or mobile homes accessory to agricultural uses as described in Section 190-23 (B) of the Talbot County Code.
 - a. The home must be manufactured after January 1, 2001 and be in compliance with the National Manufactured Home Construction and Safety Standards Act of 1974, amended.
 - b. The base width of the home for any front, side and rear elevation must be 22 feet wide and must have eaves on each side with a minimum of 1 foot overhang beyond the base width, such that the total width from eave to eave shall be at least 24 feet.
- c. The home must have a minimum 4/12 roof pitch.
- d. The roof must be finished with shingles or other conventional roofing materials common to residential construction, and the exterior siding must be similar in appearance to common residential construction.
- e. The home must have a County approved permanent continuous masonry foundation, unpierced except for required ventilation and utilities access, installed under the dwelling. The permanent masonry or brick foundation shall be left exposed or skirted with other masonry or brick.
- f. Permanent landing and steps with handrails are required at each exterior doorway.
- g. The tongue, axles, transporting lights and removable towing apparatus must be removed after placement on the lot and before occupancy.

Building Permit

- A building permit is required prior to construction of a Manufactured Home in Talbot County. A building permit application may be obtained from the Talbot County Department of Permits and Inspections located at 28712 Glebe Road, Suite 1, Easton, Maryland. Office hours are between 8:00 a.m. and 4:30 p.m. Monday – Friday. A fee for a building permit is based upon the value of the Manufactured Home. Each applicant is required to fill out the **entire** permit application and sign and date the bottom.
- To apply for a building permit, an applicant must provide four copies of a plot plan (a drawing of the property also referred to as a site plan) The plot plan shall be drawn to a standard scale (ex: 1"=10', 20', 30', 40', 50', 100') and show all property lines with dimensions, all existing structure(s), driveway, well(s), septic system, sewage disposal area(s) and the location of the proposed manufactured home. The plot plan may be prepared by the applicant or by a competent professional familiar with the application requirements provided

the drawing(s) is accurate, legible and to scale.

- Three (3) copies of the construction drawings. The construction drawings shall show all construction details as they pertain to the Manufactured Home. The following is required; Three (3) sets of plans that include, a floor plan which shows width and length of home, roof pitch information, pier footer and marriage wall footer detail diagram, footer detail diagram, information on the home, the year, make, model, purchase price.
- In addition to the building permit electrical and plumbing permits will be required for any electrical or plumbing work associated with the Manufactured Home Unit construction.
- Three inspections are required for this construction:
 1. A setback and footer inspection is required after the excavation of the trench and prior to the pouring of concrete.
 2. A foundation inspection is required after the foundation has been completed and prior to backfilling, (if required).

3. A final plumbing, electrical, and building inspection will be performed following completion of the Manufactured Home Unit and any other related construction associated with the project. To request inspections, please contact the Department of Permits and Inspections at 410-770-6840.

- Construction must begin within nine months and be completed within eighteen months.

This permit guide may not address all situations but is intended to provide general information for the permitting process.

Manufactured Home Permit Guide